



03

04









14

01 **CLOSED** 

**Diversion ENDS** 













NO ALTERNATIVE ROUTE

15



16 **ROAD AHEAD CLOSED** 



17 **ROAD AHEAD CLOSED** 









Barriers, cones and flashing lamps required each end of road closure

## CROWN COPYRIGHT DATA REPRODUCED BY PERMISSION OF THE CONTROLLER OF HMSO



ROAD CLOSURE

DIVERSION

CLOCKWISE DIVERSION ANTI-CLOCKWISE DIVERSION

ROAD CLOSURE SIGN

**ROAD CLOSURE LENGTH (APPROX)** 

2210M 3M

ROAD CLOSURE WIDTH (APPROX)

**HIRE ADVICE** 228-S006414



1. All equipment shall be approved and shall comply with the Department Of Transport specification MCE0111. This drawing does not show the normal road works signage that will be required as per Chapter 8.

2. All signs to be in accordance with TSGRD 2002 and to minimum class retroflective.

3. Minimum height of lettering to be 60mm and sign boards to be 1000mm (750mm where appropriate)

This drawing is protected by copyright and the information contained therein is confidential

This drawing may not be copied and the information therein may not be used, or disclosed to a third party, wholly or in part with the written permission of A-Plant Lux Traffic Controls Limited.

**CLIENT DETAILS** REP/DEPOT **DRAWN BY ADDRESS OPENREACH** JB/228 IC PEAR TREE LANE LAVNGTON AMEND# SHEET# DATE SN105TN 01 IC 28/01/2020 1 OF 1 03/01/2020 TIME OF WORKS OFF PEAK 24HR WORKS WEEKDAY NIGHT WEEKEND 0930-1530 2100-0600 SAT/SUN MON-FRI **BUS ROUTE AFFECTED** 

Kemble GL7 6BQ **2** 03700 500 792

**0845 004 7105** 

TRAFFIC CONTROL & MANAGEMENT

**A-Plant Lux Traffic Control & Management** Kemble Airfield Enterprise Park Cirencester Road